The 30th November 1897.

Notice is hereby given that a sum of Rs. 30-3-0 stands due in the books of this office to one Sheik Berry for work done by him on Manjarabad-Subramanya road. If Sheik Berry or his legal representative or his authorized agent fail to prefer his claim to the said amount within one month from this date, the sum will be credited to Government.

A. S. NAGAVKAR, *Exec. Engineer.*

CHITALDRUG DIVISION.

The 4th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 27th December 1897, for constructing a new tank near Gurusiddapur, Jagalur taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank near Gurusiddapur, Jagalur taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Cir who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detail of work.	*Per.*	*Quantity.*	*Remarks.*
Bund—			
Earthwork	C. yd.	34,186	
Do	,,	13,000*	*Earth from cody cutting.
Digging seat of bund	,,	4,166	
Clearing silt in the stream	,,	1,232	
Clearing jungle	Lump sum.		
Turfing	S. yd.	8,364	
Grade stone	No.	15	
B. M. stone	,,	2	
Top width stone	,,	15	
Gauge stone	,,	1	
Date stone	,,	1	
Stone revetment	C. yd.	2,989	
Weir—			
Burnt brick in chunam	C. ft.	640	
Stone in chunam	,,	581	
Apron	C. yd.	133	
Pointing	Lump sum.		
Excavating foundation and clearing draft	C. yd.	13,711	
Training bank	Lump sum.		
Channel—			
Excavation	Lump sum.		
Sluice—			
Excavation gravelly soil	C. yd.	28	
Brick in chunam	C. ft.	1,392	
Plastering with chunam	Sqr.	9·60	
Slabs	S. ft.	312	
Cut stone	Lump sum.		
Burnt stone in chunam	C. ft.	214	

K. PRAHLADA RAO, *Offg. Executive Engineer.*